

Validate Print Help

BILL OF QUANTITY

Tender Inviting Authority: Chief Executive Officer, Upelda, Lucknow

Name of Work: Providing and fixing of Stone Boundary pillar and Boundary Wall with AAC blocks around Defence Corridor periphery in Village-Sarh, Tehsil-Ghatampur, District Kanpur.

Tender Notice No: 7127/UPEIDA/ 2021

Dated: 25/11/2021

Bidder Name: M/s Suresh chand Gupta

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation in foundation in ordinary soil (Loam, Clay or Sand) including lift upto 1.50m and lead upto 30m and including filling watering and ramming of excavated earth into the trenches or into the space between the building and the sides of foundation trenches or into the plinth and removal and disposal of surplus earth as directed by the Engineer in-charge upto a distance of 30m from the foundation trenches, as per direction of Engineer-in-charge including labour cess but excluding G.S.T.	4005.97	Cum	130.00	598776.10	INR Five Lakh Ninety Eight Thousand Seven Hundred & Seventy Six and Paise Ten Only
2	Providing and laying cement concrete in 1:3:6 (1 Cement : 3 Fine sand : 3 graded stone aggregate 20 mm nominal size) including supply of all materials, labours and T&P etc. required for proper completion of the work. In Foundation, as per direction of Engineer-in-charge including labour cess but excluding G.S.T.	526.54	Cum	5600.00	2948624.00	INR Twenty Nine Lakh Forty Eight Thousand Six Hundred & Twenty Four Only
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level: 1:1.5:3 (1 cement, 1.5 coarse sand, 3 graded M20 stone aggregate 20 mm nominal size) for foundation as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	832.28	Cum	8700.00	7240836.00	INR Seventy Two Lakh Forty Thousand Eight Hundred & Thirty Six Only
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. including cost of centering, shuttering, finishing and excluding reinforcement 1:1.5:3 M20 (1 cement 1.5 coarse sand, 3 graded stone aggregate 20 mm nominal size) Above Plinth level upto fifth floor level, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	1076.40	Cum	8700.00	8929680.00	INR Eighty Nine Lakh Twenty Nine Thousand Six Hundred & Eighty Only
5	Construction of boundary wall as per drawing with providing and laying Autoclaved areated cement block masonry with (300x230x150 mm size) AAC Blocks in foundation and superstructure above plinth level upto floor 5th level with RCC framed structure with approved block laying with polymer modified adhesive mortar including providing and fixing 600 mm in dia concentric cast fencing (as per dwg) with painting and finishing the walls with exterior emulsion paint (apex) of approved brand and manufacture and of required shade complete etc. as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	4128.87	Cum	5158.00	21296711.46	INR Two Crore Twelve Lakh Ninety Six Thousand Seven Hundred & Eleven and Paise Forty Six Only
6	Mild steel or iron work in plain work such as reinforced concrete or reinforced brick work (When not included in and on over all rates) brought to required shape as necessary including bending for proper completion of the work and excluding the supply of steel and its wastage Bend hooks and authorized over lapping shall be measured upto floor to level, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	2187.69	Qlt	6180.00	13519924.20	INR One Crore Thirty Five Lakh Nineteen Thousand Nine Hundred & Twenty Four and Paise Twenty Only



7	Mild steel or iron work in heavy sizes such as built up gates, record rack, roof work, gates etc. brought to required form including drilling holes riveting or welding where necessary, and also including supply of steel bolts, nuts, wastage etc. and their fixing required for proper completion of the work, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T. size 50X50X6	18757.27	Kg	52.00	1162950.74	INR Eleven Lakh Sixty Two Thousand Nine Hundred & Fifty and Paise Seventy Four Only
8	Providing and fixing concertina coil fencing with punched tape concertina coil 600mm dia 10 metre openable length (total length 90m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron "Y" shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I staples and G.I clips to retain horizontal, including necessary bolts or G.I barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) Spring core (2.5mm thick) wire of high tensile strength of 165kg/sq.mm with tape (0.52 mm thick) and weight 43.478 gm/metre (cost of M.S. angle, C.C blocks shall be paid separately) as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	7343.70	Rmt	201.43	1479241.49	INR Fourteen Lakh Seventy Nine Thousand Two Hundred & Forty One and Paise Forty Nine Only
9	Applying priming coat over new steel and other surface upto 10 cm. in width or girth or small not exceeding 0.10 sqm area after and including preparing the surface by thoroughly clearing oil, grease, dirt and other foreign matter and scoured with wire brushed fine steelwood. Strapper, sand papering and knotting including cost of all materials, labour T&P etc. required for proper completion of work. Painting Two coats as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	678.56	Sqm	88.00	59713.28	INR Fifty Nine Thousand Seven Hundred & Thirteen and Paise Twenty Eight Only
10	Finishing walls (Two coats) with exterior emulsion paint (Apex) of approved brand and manufacture and of required shade on undercoated wall surface to give even shade @ 1.25 l/10sqm including one coat of primer applied @ 0.75 l/10sqm curing cost of all materials, labour T&P etc. required for proper completion of work, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	37222.02	Sqm	112.00	4168866.24	INR Forty One Lakh Sixty Eight Thousand Eight Hundred & Sixty Six and Paise Twenty Four Only
11	Clearing jungle including uprooting of rank vegetation, grass, bush, shrubs, saplings of girth up to 300 mm, measured at height of 1m above ground level & removal of rubbish upto a distance of 50m out side the periphery of area cleared, cost of all materials, labour T&P etc. required for proper completion of work, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	2170000.00	Sqm	5.00	10850000.00	INR One Crore Eight Lakh Fifty Thousand Only
12	Supply and fixing of machine cut stone boundary pillars of 900 mm x 150 mm x 150 mm size as per design IRC 25-1967, fixing in position with PCC M15 including finishing and lettering but excluding painting, transportation of all material, labour and all machinery (As per attached drawing.) T&P etc. required for proper completion of work, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	2400.00	Nos	1183.81	2841144.00	INR Twenty Eight Lakh Forty One Thousand One Hundred & Forty Four Only
Total in Figures					75096467.51	Seven Crore Fifty Lakh Ninety Six Thousand Four Hundred & Sixty Seven and Paise Fifty One Only
Quoted Rate in Figures			Less (-)	2.9700%	72866102.43	INR Seven Crore Twenty Eight Lakh Sixty Six Thousand One Hundred & Two and Paise Forty Three Only
Quoted Rate in Words		INR Seven Crore Twenty Eight Lakh Sixty Six Thousand One Hundred & Two and Paise Forty Three Only				



by
A.E.
28/12/2021

20/12/21



25/12/21



Validate Print Help

BILL OF QUANTITY

Tender Inviting Authority: Chief Executive Officer, Upelda, Lucknow

Name of Work: Providing and fixing of Stone Boundary pillar and Boundary Wall with AAC blocks around Defence Corridor periphery in Village-Sarh, Tehsil-Ghatampur, District Kanpur.

Tender Notice No: 7127/UPEIDA/ 2021

Dated. 25/11/2021

BIDDER NAME: M/S HARI CONSTRUCTION						
PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only.)						
NUMBER	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER	TEXT #
SL No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Excavation in foundation in ordinary soil (Loam, Clay or Sand) including lift upto 1.50m and lead upto 30m and including filling watering and ramming of excavated earth into the trenches or into the space between the building and the sides of foundation trenches or into the plinth and removal and disposal of surplus earth as directed by the Engineer in-charge upto a distance of 30m from the foundation trenches as per direction of Engineer-in-charge including labour cess but excluding G.S.T.	4605.97	Cum	130.00	598776.10	INR Five Lakh Ninety Eight Thousand Seven Hundred & Seventy Six and Paise Ten Only
2	Providing and laying cement concrete in 1:3:6 (1 Cement : 3 Fine sand : 3 graded stone aggregate 20 mm nominal size) including supply of all materials, labours and T&P etc. required for proper completion of the work. In Foundation as per direction of Engineer-in-charge including labour cess but excluding G.S.T.	526.54	Cum	5600.00	2948624.00	INR Twenty Nine Lakh Forty Eight Thousand Six Hundred & Twenty Four Only
3	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement. All work up to plinth level. 1:1.5:3 (1 cement : 1.5 coarse sand : 3 graded M20 stone aggregate 20 mm nominal size) for foundation as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	832.28	Cum	8700.00	7240836.00	INR Seventy Two Lakh Forty Thousand Eight Hundred & Thirty Six Only
4	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. including cost of centering, shuttering, finishing and excluding reinforcement 1:1.5:3 M20 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20 mm nominal size) Above Plinth level upto fifth floor level, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	1026.40	Cum	8700.00	8929680.00	INR Eighty Nine Lakh Twenty Nine Thousand Six Hundred & Eighty Only
5	Construction of boundary wall as per drawing with providing and laying Autoclaved aerated cement block masonry with (300x230x150 mm size) AAC Blocks in foundation and superstructure above plinth level upto floor 5th level with RCC framed structure with approved block laying with polymer modified adhesive mortar including providing and fixing 600 mm in dia concrete column (as per dwg) with painting and finishing the walls with exterior emulsion paint (apex) of approved brand and manufacture and of required shade complete etc. as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	4128.87	Cum	5158.00	21298711.46	INR Two Crore Twelve Lakh Ninety Six Thousand Seven Hundred & Eleven and Paise Forty Six Only
6	Mild steel or iron work in plain work such as reinforced concrete or reinforced brick work (When not included in and on over all rates) brought to required shape as necessary including bending for proper completion of the work and excluding the supply of steel and its wastage Bend, hooks and authorized over lapping shall be measured upto floor to level, as per direction of Engineer-in-charge, including labour cess but excluding G.S.T.	2187.69	Qtr	6180.00	13519924.20	INR One Crore Thirty Five Lakh Nineteen Thousand Nine Hundred & Twenty Four and Paise Twenty Only



20/12/21
GT



7	Mild steel or iron work in heavy sizes such as built up gates, record rack, roof work, gates etc. brought to required from including drilling holes, riveting or welding where necessary, and also including supply of steel bolts, nuts, wastage etc. and their fixing required for proper completion of the work, as per direction of Engineer-in-charge. Including labour cess but excluding G.S.T. size 50X50X6	18757.27	Kg	62.00	1162950.74	INR Eleven Lakh Sixty Two Thousand Nine Hundred & Fifty and Paise Seventy Four Only
8	Providing and fixing concertina coil fencing with punched tape concertina coil 600mm dia 10 metre openable length (total length 90m), having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I staples and G.I clips to retain horizontal, including necessary bolts or G.I barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape (R.B.T.) Spring core (2.5mm thick) wire of high tensile strength of 165kg/sq mm with tape (0.52 mm thick) and weight 43.478 gmv/metre (cost of M.S. angle, C.C blocks shall be paid separately) as per direction of Engineer-in-charge. including labour cess but excluding G.S.T.	7343.70	Rmt	201.43	1479241.49	INR Fourteen Lakh Seventy Nine Thousand Two Hundred & Forty One and Paise Forty Nine Only
9	Applying priming coat over new steel and other surface upto 10 cm. in width or girth or small not exceeding 0.10 sqm area after and including preparing the surface by thoroughly clearing oil, grease, dirt, and other foreign matter and scoured with wire brushed, fine steel/wood. Strapper, sand papering and knotting including cost of all materials, labour T&P etc. required for proper completion of work. Painting Two coats as per direction of Engineer-in-charge. including labour cess but excluding G.S.T.	678.56	Sqm	88.00	59713.28	INR Fifty Nine Thousand Seven Hundred & Thirteen and Paise Twenty Eight Only
10	Finishing walls (Two coats) with exterior emulsion paint (Apex) of approved brand and manufacture and of required shade on undercoated wall surface to give even shade @ 1.25 l/10sqm including one coat of primer applied @ 0.75 l/10sqm curing, cost of all materials, labour T&P etc. required for proper completion of work, as per direction of Engineer-in-charge. including labour cess but excluding G.S.T.	37222.02	Sqm	112.00	4168866.24	INR Forty One Lakh Sixty Eight Thousand Eight Hundred & Sixty Six and Paise Twenty Four Only
11	Clearing jungle including uprooting of rank vegetation, grass, bush, shrubs, saplings of girth up to 300 mm. measured at height of 1m above ground level & removal of rubbish upto a distance of 50m out side the periphery of area cleared, cost of all materials, labour T&P etc. required for proper completion of work, as per direction of Engineer-in-charge. including labour cess but excluding G.S.T.	2170000.00	Sqm	5.00	10850000.00	INR One Crore Eight Lakh Fifty Thousand Only
12	Supply and fixing of machine cut stone boundary pillars of 900 mm x 150 mm x 150 mm size as per design IRC 25-1967. fixing in position with PCC M15 including finishing and lettering but excluding painting, transportation of all material, labour and all machinery (As per attached drawing.) T&P etc. required for proper completion of work, as per direction of Engineer-in-charge. including labour cess but excluding G.S.T.	2400.00	Nos	1183.81	2841144.00	INR Twenty Eight Lakh Forty One Thousand One Hundred & Forty Four Only
Total in Figures					75096467.51	Seven Crore Fifty Lakh Ninety Six Thousand Four Hundred & Sixty Seven and Paise Fifty One Only
Quoted Rate in Figures			Excess (+)	4.0000%	78100326.21	INR Seven Crore Eighty One Lakh Three Hundred & Twenty Six
Quoted Rate in Words		INR Seven Crore Eighty One Lakh Three Hundred & Twenty Six and Paise Twenty One Only				



for
AE.
28/12/2021

20/12/21
GCE



25.12.21
SE



BOQ Summary Details
Tender Title: Providing and fixing of Stone Boundary pillar and Barbed wire fencing around Defence Corridor periphery in Village-Andala, Tehashil-Khair, District-Allgarh
Tender ID: 2021_UPEID_649294_1

Sheet Name	Sl.No	Bidder Name	Amount	Bid Rank
BoQ1	1	SURESH GUPTA	72866102.43	L1
	2	M/s HARI CONSTRUCTION	78100326.21	L2

Handwritten signature
 28.12.21
 8.12

Handwritten signature
 28/12/21
 67

Handwritten signature
 28/12/2021





eProcurement System Government of Uttar Pradesh
Created By: MANOJ KUMAR SINGH
Created Date/Time: 28-Dec-2021 04:14 PM
Tender Title: Providing and fixing of Stone Boundary pillar and Barbed wire fencing around Defence Corridor periphery in Village-Andala, Tehashil-Khair, District-Allgarh
Tender ID: 2021_UPEID_649294_1

Tender Inviting Authority: Chief Executive Officer, Upeida, Lucknow
Name of Work: Providing and fixing of Stone Boundary pillar and Boundary Wall with AAC blocks around Defence Corridor periphery in Village-Sarh, Tehasil-Ghatampur, District Kanpur.
Tender Notice No: 7127/UPEIDA/ 2021 Dated. 25/11/2021

SL.No	Bidder Name	Estimated Rate	Quoted Percentage	Rate	Amount
1.00	SURESH GUPTA(GSTN-09AAFFS9843N1ZB)	75096467.51	-2.97	72866102.43	Seven Crore Twenty Eight Lakh Sixty Six Thousand One Hundred and Two
2.00	Ms HARI CONSTRUCTION(GSTN-NA)	75096467.51	4.00	78100326.21	Seven Crore Eighty One Lakh Three Hundred and Twenty Six

Lowest Amount Quoted BY: SURESH GUPTA(72866102.43)

for 28/12/21
28/12/21
28/12/21
28/12/21

पत्रांक-7997/2021/यूपीडा/2021

दिनांक-28/12/2021

कार्यालय ज्ञाप

इस कार्यालय के ई-निविदा आमंत्रण सूचना पत्रांक-7127/यूपीडा/तक. दिनांक 25/11/2021 द्वारा डिफेंस इन्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाक मेसेनरी द्वारा बाउन्ड्री वॉल के कार्य की ई-निविदा आमंत्रित की गयी थी। ई-निविदा दिनांक 08/12/2021 को अपरान्ह 12:00 बजे तक प्राप्त की गयी, जिनकी तकनीकी बिड दिनांक 08/12/2021 को अपरान्ह 3:30 बजे खोली गयी। जिसमें कुल 04 निविदाएं अपलोड पायी गयी। अपलोड निविदाओं का तकनीकी मूल्यांकन उपरान्त 02 निविदाएं रिस्पॉन्सिव एवं 02 निविदाएं नॉन-रिस्पॉन्सिव पायी गयीं। जिसका विवरण निम्नवत है-

क्र० सं०	कार्य का नाम	प्राप्त कुल निविदाओं की संख्या	रिस्पॉन्सिव/पात्र पाये गये निविदाओं की संख्या	रिस्पॉन्सिव/पात्र पाये गये निविदादाता
1	डिफेंस इन्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाक मेसेनरी द्वारा बाउन्ड्री वॉल का कार्य।	04	02	मै. सुरेश चन्द गुप्ता, 60 गणेश बाजार, झाँसी। मै. हरी कन्स्ट्रक्शन, IInd फ्लोर, वैष्णों मार्केट, बस स्टैण्ड, बारागाँव, झाँसी।

उपरोक्त कार्य की वित्तीय बिड दिनांक 28/12/2021 को अपरान्ह 03:30 बजे खोला जाना प्रस्तावित है।

मुख्य कार्यपालक अधिकारी
यूपीडा, लखनऊ

पत्रांक-

यूपीडा/

दिनांक-

,2021

प्रतिलिपि:-

- मुख्य महाप्रबन्धक (तकनीकी), डिफेंस कॉरीडोर, यूपीडा, लखनऊ, को सूचनार्थ प्रेषित।
- मै. सुरेश चन्द गुप्ता, 60 गणेश बाजार, झाँसी को सूचनार्थ प्रेषित।
- मै. हरी कन्स्ट्रक्शन, IInd फ्लोर, वैष्णों मार्केट, बस स्टैण्ड बारागाँव, झाँसी को सूचनार्थ प्रेषित।

मुख्य कार्यपालक अधिकारी
यूपीडा, लखनऊ



यूपीडा

उत्तर प्रदेश एक्सप्रेसवेज इन्डस्ट्रियल डेवलपमेन्ट अथॉरिटी
सी-13, द्वितीय तल, पर्यटन भवन, विपिन खण्ड, गोमतीनगर, लखनऊ-226010
☎ 0522-2307542 / 2307592 / 4108184, फ़ैक्स 0522-2301142.
ईमेल: tc.upeida2@gmail.com

पत्रांक-7997 यूपीडा/

दिनांक-28/12/2021

कार्यालय ज्ञाप

इस कार्यालय के ई-निविदा आमंत्रण सूचना पत्रांक-7127/यूपीडा/तक. दिनांक 25/11/2021 द्वारा डिफेंस इन्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल के कार्य की ई-निविदा आमंत्रित की गयी थी। ई-निविदा दिनांक 08/12/2021 को अपराह्न 12:00 बजे तक प्राप्त की गयी, जिनकी तकनीकी बिड दिनांक 08/12/2021 को अपराह्न 3:30 बजे खोली गयी। जिसमें कुल 04 निविदाएं अपलोड पायी गयी। अपलोड निविदाओं का तकनीकी मूल्यांकन उपरान्त 02 निविदाएं रिस्पॉन्सिव एवं 02 निविदाएं नॉन-रिस्पॉन्सिव पायी गयीं। जिसका विवरण निम्नवत है-

क्र० सं०	कार्य का नाम	प्राप्त कुल निविदाओं की संख्या	रिस्पॉन्सिव/पात्र पाये गये निविदाओं की संख्या	रिस्पॉन्सिव/पात्र पाये गये निविदादाता
1	डिफेंस इन्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल का कार्य।	04	02	मै. सुरेश चन्द गुप्ता, 60 गणेश बाजार, डाँसी। मै. हरी कन्स्ट्रक्शन, IInd फ्लोर, वैष्णो मार्केट, बस स्टैण्ड, बारागाँव, डाँसी।

उपरोक्त कार्य की वित्तीय बिड दिनांक 28/12/2021 को अपराह्न 03:30 बजे खोला जाना प्रस्तावित है।

मुख्य कार्यपालक अधिकारी
यूपीडा, लखनऊ

दिनांक- .2021

पत्रांक-

प्रतिलिपि:-

- मुख्य महाप्रबन्धक (तकनीकी), डिफेंस कॉरीडोर, यूपीडा, लखनऊ, को सूचनार्थ प्रेषित।
- मै. सुरेश चन्द गुप्ता, 60 गणेश बाजार, डाँसी को सूचनार्थ प्रेषित।
- मै. हरी कन्स्ट्रक्शन, IInd फ्लोर, वैष्णो मार्केट, बस स्टैण्ड बारागाँव, डाँसी को सूचनार्थ प्रेषित।



मुख्य कार्यपालक अधिकारी
यूपीडा, लखनऊ



सेवा में,

मुख्य कार्यपालक अधिकारी,
यूपीडा, लखनऊ।

विषय:- डिफेंस इण्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल का कार्य।

सन्दर्भ:- आपका ई-निविदा पत्रांक 7127/यूपीडा/तक. दिनांक 25/11/2021
महोदय,

उपरोक्त विषय सन्दर्भित ई-निविदा के सम्बन्ध में अवगत कराना है कि वित्तीय वर्ष 2021-22 में अनुदान संख्या-07 के अधीन लेखा शीर्षक-5054 सड़कों तथा सेतुओं पर पूंजीगत परियोजना-03, राज्य राजमार्ग-337, सड़क निर्माण कार्य योजना-08, बुन्देलखण्ड एक्सप्रेसवे परियोजना के साथ डिफेंस कॉरीडोर के 24 वृहद निर्माण कार्य के अन्तर्गत डिफेंस इण्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल के कार्य की स्वीकृति शासनादेश संख्या 38/2021/985/77-3-2021-136(एम)/21, औद्योगिक विकास अनुभाग-3 दिनांक 30/07/2021 के द्वारा रु. 950.13 लाख की प्राप्त हुई है। उक्त कार्य की तकनीकी स्वीकृति मुख्य अभियन्ता, यूपीडा, लखनऊ के कार्यालय-ज्ञाप पत्रांक 6479/यूपीडा/21/1989/तकनीकी दिनांक 29/10/2021 के द्वारा रु. 848.65 लाख की प्रदान की गई। उक्त विषयक कार्य की ई-निविदा आपके पत्रांक 7127/यूपीडा/तक. दिनांक 25/11/2021 द्वारा आमंत्रित की गई। उक्त निविदा निविदा दिनांक 08/12/2021 पूर्वान्ह 12:00 बजे तक प्राप्त की गई एवं प्राप्त निविदा दिनांक 08/12/2021 अपराह्न 3:30 बजे खोली गई। उक्त कार्य की कुल 04 ई-निविदाएँ अपलोड पायीं गयीं। अपलोड निविदाओं का तकनीकी मूल्यांकन उपरान्त 02 निविदाएँ रिसपॉन्सिव एवं 02 निविदाएँ नॉन रिसपॉन्सिव पायीं गयीं (मूल्यांकन प्रपत्र संलग्न)। जिनका विवरण निम्नलिखित है:-

क्र० सं०	कार्य का नाम	प्राप्त कुल निविदाओं की संख्या	रिसपॉन्सिव/पात्र पाये गये निविदाओं की संख्या	रिसपॉन्सिव/पात्र पाये गये निविदादाता
1	डिफेंस कॉरीडोर के अन्तर्गत डिफेंस इण्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल का कार्य।	04	02	मै. सुरेश चन्द गुप्ता, 60 गणेश बाजार, झाँसी। मै. हरी कन्स्ट्रक्शन, IInd फ्लोर, वैष्णो मार्केट, बस स्टैण्ड, बारागाँव, झाँसी।

अतः उपरोक्त कार्य की वित्तीय बिड दिनांक 28/12/2021 को अपराह्न 3:30 बजे खोलने के कार्यालय ज्ञाप का ड्राफ्ट संलग्न कर प्रेषित है।

संलग्नक:- उपरोक्तानुसार।

अधिशासी अभियन्ता
पी.आई.यू.-1, यूपीडा, आगरा

दिनांक-

पत्रांक -

प्रतिनिधि - मुख्य महाप्रबन्धक (तकनीकी), डिफेंस कॉरीडोर, यूपीडा, लखनऊ को सूचनार्थ हेतु प्रेषित।



अधिशासी अभियन्ता
पी.आई.यू.-1, यूपीडा, आगरा

TECHNICAL BID EVALUATION REPORT (For works Above Rs. 500.00 Lac.)

Date of Opening Bid :- 08-12-2021

Number of Bids received :- 04

Details of calling Bid :- 25-11-2021
 Opening Bid :- 08-12-2021
 Bid :- Rs. 752.80 Lacs.

providing and fixing of Stone Boundary pillar and Boundary wall with ACC blocks around defence corridor periphery in village-Sarh, Tehsil-Ghatampur, District-Kanpur.

DETAILS OF BID		Requirement as per bid	Name of contractor	Name of contractor	Name of contractor	Remark
Sl No						
1	2	3	4	5	6	7
1	Bid Security Details		M/s. Suresh Chand Gupta, 60 Ganesh Bazar, Jhansi	M/s. Hart Constructions	M/s. Ganga Infra Build Pvt. Ltd.	
	Name of Bank (Nationalized bank)		Yes Bank Ltd. Jhansi	Punjab and Sind Bank, Jhansi	3, Harinder Nagar, Kanpur	
	No. of Security	One	1	1	1	
	Amount	Rs. 15.10 Lacs.	Rs. 15.30 Lakhs	Rs. 15.10 Lakhs	Rs. 15.10 Lakhs	
	Security Valid up to		04.12.2023	07.06.2022	07.12.2022	
	Tender Fee (G.D.)	Rs. 2714.00	Rs. 2714/- D.D.	Rs. 2714/- D.D.	Rs. 2714/- D.D.	
	Bid Validity	120 Days	Attached Rs. 100/- Stamp	Attached Rs. 100/- Stamp	Attached Rs. 100/- Stamp	
2	Character Certificate on P.W.D. T-4		Attached date 12.08.2023	Attached date 06.11.2022	Attached date 27.02.2024	
3	Solvency Certificate on P.W.D. T-5		Attached date 17.03.2023	Attached 06.06.2023	Attached 14.07.2022	
4	Certificate of Registration in U.P. P.W.D.		Attached date 30.06.2022	Attached 30.06.2022	Attached date 30.06.2023	
5	Self declaration affidavit on P.W.D. T-6		Attached	Attached	Not Attached	
6	Section -2		Attached	Attached	Attached	
7	Constitution or legal status of Bidder		Attached but all blank	Proprietorship Firm attached power of attorney	Ganga Infra Build Pvt. Ltd. (Not in Rs. 100/- Stamp)	
8	Place of registration			Lucknow	Lucknow	
9	Principal Place of Business			Jhansi	Not Attached	
10	Power of attorney of Signatory of bid			M/s. Suresh Chand Gupta	Not Attached	
11	Total annual volume of civil engineering construction work executed and payments received in the last five years preceding the year in which bids are invited (Certificate from Chartered Accountant) Rs. 752.00 Lacs.	2015-16 2016-17 2017-18 2018-19 2019-20	Rs. 4531.00 Lakhs Rs. 6252.00 Lakhs Rs. 2908.00 Lakhs Rs. 5079.00 Lakhs Rs. 7648.00 Lakhs	Rs. 10142.00 Lakhs Rs. 7988.00 Lakhs Rs. 13901.00 Lakhs Rs. 2243.00 Lakhs Rs. 2148.00 Lakhs	Rs. 2097.00 Lakhs Rs. 2328.00 Lakhs Rs. 1951.00 Lakhs Rs. 1612.00 Lakhs Rs. 1141.00 Lakhs	Rs. 2757.86 Lakhs Rs. 2489.16 Lakhs Rs. 2527.41 Lakhs Rs. 4617.72 Lakhs Rs. 8014.35 Lakhs
12	Bid Capacity (A+B+C+D+E) Rs. Lacs	752.00 Lakhs	Rs. 7249.00 Lakhs (Not attached in Rs. 100/- Stamp)	Rs. 27014.74 Lakhs	Rs. 5432.00 Lakhs	Not Attached
13	Experience of satisfactory completed work as a joint venture in last one similar work in last five years in the prescribed format. Attach certificate from Employer for charge.	1.7 Equal to Value of estimated Cost in any one year	Rs. 2876.00 Lakhs	Rs. 1962.30 Lakhs	Rs. 539.26 Lakhs	Rs. 829.84 Lakhs

Signature

20/12/2021

A circular library stamp from Suresh Chand Gupta. The outer ring contains the name "SURESH CHAND GUPTA" at the top and "60 Gandhi Bazar, Patna-8" at the bottom, separated by two small stars. In the center, there is a vertical date stamp that reads "1970". A diagonal line crosses the stamp from the top right towards the center.

20.12.21
852

2

173



Uttar Pradesh Tenders

eProcurement System Government of Uttar Pradesh

Bid Opening Summary

Date : 08-Dec-2021 03:58 PM

Print

Organisation Chain :	U.P. Expressways Industrial Development Authority
Tender ID :	2021_UPEID_649294_1
Tender Ref No :	7127/upelda/tech
Tender Title :	Providing and fixing of Stone Boundary pillar and Barbed wire fencing around Defence Corridor periphery in Village-Andala, Tehashil-Khair, District-Aligarh
Packet Name :	Fee/PreQual/Technical

Decrypted Bid Openers List

S.No	Name	Decrypted Date
1	Kishore Kumar Pande	08-Dec-2021 03:39 PM
2	MANOJ KUMAR SINGH	08-Dec-2021 03:42 PM

Bid List

S.No	Bid No	Bidder	Opened By	Opened Date	Status
1	2628937	M/S MITTAL BROTHERS ENGINEERS AND	MANOJ KUMAR SINGH	08-Dec-2021 03:45 PM	Admitted
2	2636878	SURESH GUPTA	MANOJ KUMAR SINGH	08-Dec-2021 03:47 PM	Admitted
3	2637901	M/s HARI CONSTRUCTION	MANOJ KUMAR SINGH	08-Dec-2021 03:50 PM	Admitted
4	2639303	GANGA INFRABUILD PVT LTD	MANOJ KUMAR SINGH	08-Dec-2021 03:55 PM	Admitted

Bid Opening Summary

Bid Opener	Type	Summary	Updated On
MANOJ KUMAR SINGH	Technical	TENDER HAS TO BE OPENED	08-Dec-2021 03:57 PM

by
BE
8/12/2021

00/12/2021
Gt

8/12/21
S.E



<http://tenders.up.nic.in/nicgep/app?component=%24DirectLink&page=BidOpeningSum> 08-12-2021

175

Uttar Pradesh Tenders

eProcurement System Government of Uttar Pradesh

Tender Details

Date : 29-Nov-2021 05:23 PM

Print

Basic Details			
Organisation Chain	U.P. Expressways Industrial Development Authority		
Tender Reference Number	7127/upelda/tech		
Tender ID	2021_UPEID_649294_1		
Tender Type	Open Tender	Form of contract	Percentage
Tender Category	Works	No. of Covers	2
General Technical Evaluation Allowed	No	ItemWise Technical Evaluation Allowed	No
Payment Mode	Offline	Is Multi Currency Allowed For BOQ	No
Is Multi Currency Allowed For Fee	No	Allow Two Stage Bidding	No

Payment Instruments		Cover Details, No. Of Covers - 2			
Offline	S.No	Instrument Type	Cover No	Cover	Document Type
	1	DD - Demand Draft			Description
	2	FDR - Fixed Deposit	1	Fee/PreQual/Technical	.pdf
			2	Finance	.xls
					TECHNICAL PROPOSAL
					FINANCIAL PROPOSAL

Tender Fee Details, [Total Fee in ₹ * - 2,714]				EMD Fee Details			
Tender Fee in ₹	2,714	Fee Payable To	CEO UPEIDA	EMD Amount in ₹	15,10,000	EMD through BG/ST or EMD Exemption Allowed	No
Fee Payable At	Lucknow	Tender Fee Exemption Allowed	No	EMD Fee Type	fixed	EMD Percentage	NA
		EMD Payable To	CEO UPEIDA	EMD Payable At	Lucknow		

Click to view modification history

Work / Item(s)					
Title	Providing and fixing of Stone Boundary pillar and Barbed wire fencing around Defence Corridor periphery in Village-Andala, Tehashil-Khair, District-Aligarh				
Work Description	Providing and fixing of Stone Boundary pillar and Barbed wire fencing around Defence Corridor periphery in Village-Andala, Tehashil-Khair, District-Aligarh				
Pre Qualification Details	Please refer Tender documents.				
Independent External Monitor/Remarks	NA				
Show Tender Value in Public Domain	Yes				
Tender Value in ₹	7,52,00,000	Product Category	Civil Works	Sub category	NA
	Tender	Bid Validity(Days)	120	Period Of Work (Days)	240



https://up.nic.in/nicgep/app?component=24DirectLink&page=PublishedViewT.UPEID-1-2021

कार्यालय मुख्य कार्यपालक अधिकारी
उ.प्र. एक्सप्रेसवे औद्योगिक विकास प्राधिकरण(यूपीडा),
सी-13, द्वितीय तल, पर्यटन भवन, विपिन खण्ड, गौमती नगर,

पत्रांक 5127

लखनऊ

दिनांक 25/11/2021

निविदा आमंत्रण सूचना

- मुख्य कार्यपालक अधिकारी, यूपीडा, लखनऊ, द्वारा निम्न तालिका में अंकित विवरण के अनुसार योग्य एवं लोक निर्माण विभाग, उ.प्र. में पंजीकृत ठेकेदारों से प्रतिशत आधारित ऑन लाईन निविदा आमंत्रित की जाती है। निविदादाताओं को सलाह दी जाती है कि निविदा डालने से पूर्व एस0बी0डी0 की निविदा दस्तावेजों में निविदादाताओं को निर्देश, निविदा की सामान्य शर्तें, कान्ट्रैक्ट डाटा, निविदा में दिये गये प्रारूप, अन्य शर्तें, तकनीकी विशिष्टियों, बिल ऑफ़ क्वांटिटी एवं एडेन्डम/एमेन्डमेंट्स आदि का ध्यानपूर्वक अध्ययन कर लिया जाये।

निविदादाताओं को सलाह दी जाती है कि निविदा में योग्य पाए जाने हेतु ITB के क्लॉज 4 में वर्णित न्यूनतम योग्यता मापदण्डों पर ध्यान दें।

क्र. सं.	कार्य का नाम	अनुमानित लागत (लाख रु. में)	धरोहर राशि (लाख रु. में)	निविदा प्रपत्र का मूल्य (रु. में)	कार्य निष्पादित करने वाले अधिशासी अभियन्ता का पता
1	डिफेंस इन्डस्ट्रियल कॉरीडोर के अन्तर्गत जनपद-कानपुर के ग्राम-साढ़, तहसील-घाटमपुर में अधिग्रहीत भूमि की सुरक्षा हेतु स्टोन बाउन्ड्री पिलर एवं ऑटोक्लेड एरियेटेड सीमेन्ट ब्लाकड मेसेनरी द्वारा बाउन्ड्री वॉल के निर्माण का कार्य।	752.00	15.10	रु. 2300.00 + 18% जीएसटी = रु.2714.00	पी.आई.यू.-1, यूपीडा, 89-90 ब्लाक बी-1, ताजनगरी फेस-2, (सी.एन.जी. पम्प के पीछे) फतेहाबाद रोड, आगरा-282001

- निविदा दस्तावेज एवं निविदा हेतु आमंत्रण की विस्तृत एवं शर्तें वेबसाइट <http://etender.up.nic.in> पर ऑनलाइन उपलब्ध है।
- निविदा से सम्बन्धित समस्त दस्तावेज वेबसाइट <http://etender.up.nic.in> दिनांक 23/11/2021 से 07/12/2021 की अवधि में 12.00 बजे अपरान्ह तक उपलब्ध रहेगी। निविदा वेबसाइट <http://etender.up.nic.in> पर दिनांक 08/12/2021 को 12.00 बजे अपरान्ह तक अपलोड की जा सकती है। ऑनलाइन प्राप्त टैक्निकल निविदा दिनांक 08/12/2021 को 03:30 बजे अपरान्ह खोली जायेगी।
- प्रत्याशित निविदादाता जिसने डिजिटल सिग्नेचर प्रमाण पत्र प्राप्त न किया हो, वह प्रमाणित एजेन्सी से प्राप्त कर सकता है।

मुख्य कार्यपालक अधिकारी
यूपीडा, लखनऊ

